



ECS Southwest, LLP

Geotechnical Engineering Report

Zaxby's Restaurant Development

North of 19140 I-35

Kyle, Texas

ECS Project Number 17:5744

November 22, 2021





November 22, 2021

Avant Foods, Inc.
c/o
Mr. Jeff Carter, P.E.
Carter Engineering Consultants, Inc
3651 Mars Hill Road, Suite 2000
Watkinsville, Georgia 30677

ECS Project No. 17:5744

Reference: Geotechnical Engineering Report
Zaxby's Restaurant Development
North of 19140 I-35
Kyle, Texas

Dear Mr. Carter:

ECS Southwest, LLC (ECS) has completed the subsurface exploration, laboratory testing, and geotechnical engineering analyses for the above referenced project. Our services were performed in general accordance with the Project Authorization Agreement (ECS Proposal No. 17-7383), dated October 22, 2021. This report presents our understanding of the geotechnical aspects of the project along with the results of the field exploration and laboratory testing conducted, and our design and construction recommendations.

It has been our pleasure to be of service to you during the design phase of this project. We would appreciate the opportunity to remain involved during the continuation of the design phase, and we would like to provide our services during construction phase operations as well to verify the subsurface conditions considered for this report. Should you have any questions concerning the information contained in this report, or if we can be of further assistance to you, please contact us.

Respectfully submitted,

ECS Southwest, LLP

Connor Roman, P.E.
Department Manager
croman@ecslimited.com



Michael Sorgenfrei, P.E., P.G.
Principal, Branch Manager
msorgenfrei@ecslimited.com

Electronic seal approved by Connor Roman, P.E. on November 22, 2021

Timothy Moody, P.E.
Geotechnical Project Manager



ECS SOUTHWEST, LLP

lmooody@ecslimited.com

Geotechnical • Construction Materials • Environmental • Facilities

"Setting the Standard for Service"

TX Registered Engineering Firm F-8461

TABLE OF CONTENTS

EXECUTIVE SUMMARY	1
1.0 INTRODUCTION	2
1.1 General	2
2.0 PROJECT INFORMATION	3
2.1 Project Location/Current Site Use/Past Site Use	3
2.2 Proposed Construction.....	3
3.0 FIELD EXPLORATION AND LABORATORY TESTING	5
3.1 Subsurface Characterization	5
3.2 Groundwater Observations.....	5
3.3 Laboratory Testing	6
4.0 DESIGN RECOMMENDATIONS	7
4.1 Potential Vertical Rise & Subgrade Improvements.....	7
4.2 Shallow Foundations	8
4.2.1 Slab-on-Grade Foundations.....	8
4.3 Perimeter Conditions	9
4.4 Seismic Design Considerations.....	10
4.5 Retaining Walls.....	11
4.6 Pavement Sections – Private Drives and Parking.....	13
4.6.1 Pavement Materials.....	14
4.6.2 Rigid Pavement Considerations	15
4.6.3 Pavement Drainage, Subdrainage, and Trenching	16
5.0 SITE CONSTRUCTION RECOMMENDATIONS	17
5.1 Subgrade Preparation	17
5.1.1 Removals, Stripping and Grubbing	17
5.1.2 Proof Rolling	17
5.1.3 Site Temporary Dewatering.....	18
5.2 Earthwork Operations	19
5.3 Material Specifications.....	20
5.3.1 General Fill	20
5.3.2 Select Fill	21
5.3.3 Moisture Conditioned Fill	21
5.4 Foundation and Slab Observations	21
5.5 Utility Installations	22
6.0 CLOSING.....	24

APPENDICES

Appendix A – Figures

- Site Location Diagram
- Boring Location Diagram
- Generalized Subsurface Soil Profile
- Site Geologic Map

Appendix B – Field Operations

- Boring Logs B-01 to B-03
- Reference Notes for Boring Logs

Appendix C – Laboratory Testing

- Laboratory Testing Summary
- Grain Size Distributions

Appendix D – Supplemental Report Documents

- Clay Plug Detail

EXECUTIVE SUMMARY

The following summarizes the main findings of the exploration, particularly those that may have a cost impact on the planned development. Further, our principal geotechnical recommendations are summarized. Information gleaned from the executive summary should not be utilized in lieu of reading the entire geotechnical report.

- The predominant geotechnical and geological constraint that needs to be addressed at the site is the highly expansive soil conditions.
- Several methods exist to evaluate swell potential of expansive clay soils. We have estimated potential heave in the proposed building areas utilizing the TxDOT PVR method (Tex 124-E). We estimate the existing PVR in the proposed building area to be about 6 inches.
- To mitigate soil expansion potential in the proposed building to about 1 inch, it is recommended that the building pad be improved according to this report's Section 4.1 "Potential Vertical Rise & Subgrade Improvements".
- The proposed building can be founded on a monolithic beam and slab-on-grade foundation system. Grade beams and widened column areas at least 10 inches wide and 18 inches deep can be designed using a net allowable bearing capacity of 3,000 psf.
- Light duty pavements can consist of 2 inches asphaltic concrete on 10 inches base on a prepared subgrade, or 5 inches concrete on a prepared subgrade. Moderate duty pavements can consist of 2½ inches asphaltic concrete on 12 inches base on a prepared subgrade, or 6 inches concrete on a prepared subgrade. Heavy duty pavements can consist of 7 inches concrete on a prepared subgrade.
- It is recommended that ECS conduct a geotechnical review of the project plans (prior to issuance for construction) to check to see that ECS' geotechnical recommendations have been properly interpreted and implemented.
- To prevent misinterpretation of our recommendations, ECS should be retained to perform quality control testing and documentation during construction of the earthwork and foundations for the project.

1.0 INTRODUCTION

1.1 GENERAL

The purpose of this study was to provide geotechnical information for the design of foundations for a single-story Zaxby's restaurant building with a footprint of 3,652 square feet, and associated private drive lanes and appurtenances. Geotechnical recommendations for associated retaining walls, utility improvements, surface parking and pavements are also included in this project.

Our services were provided in accordance with the Project Authorization Agreement document (ECS Proposal No. 17-7383) dated October 22, 2021. This study was authorized on October 22, 2021 by Mr. Jeff Carter of Carter Engineering Consultants, LLC, via signature of the referenced agreement.

The report includes the following items.

- A brief review and description of our field and laboratory test procedures and the results of testing conducted.
- A review of surface topographical features and site conditions.
- A review of area and site geologic conditions.
- A review of subsurface soil stratigraphy with pertinent available physical properties.
- A final copy of our soil test borings.
- Recommendations for site preparation, grading, and drainage.
- Recommendations for foundation design and construction.
- Recommendations for retaining wall design and construction.
- Recommendations for pavement design and construction.

2.0 PROJECT INFORMATION

2.1 PROJECT LOCATION/CURRENT SITE USE/PAST SITE USE

The project site is generally located just south of the existing Home Depot building and west of I-35 in Kyle, Texas. The location is depicted in Figure 2.1.1 as shown below.



Figure 2.1.1 Site Location

The approximately 1-acre site consists of undeveloped grassland. Existing topographic information was not provided at the time of this report. The subject site appears to have been historically used as farmland.

2.2 PROPOSED CONSTRUCTION

According to the site plan prepared by Carter Engineering Consultants, it is understood that the proposed development will consist of a 3,652 square foot building, associated drive and fire lanes, and appurtenances.

SUBJECT	DESIGN INFORMATION / ASSUMPTIONS
	BUILDING
Approximate Building Footprints	3,652 square feet
# of Stories	1 story above grade
Usage	Restaurant
Column Loads	Not provided, < 50 kips Assumed
Wall Loads	Not provided, < 2 kips/ft Assumed
Building Finished Floor Elevation	Not provided. Considered to be within 5 feet of existing site grades

If ECS' understanding of the project is not correct, especially if the structural loads are different, please contact ECS so that we may review these changes and revise our recommendations as appropriate.

3.0 FIELD EXPLORATION AND LABORATORY TESTING

Our subsurface findings and procedures are included in Appendix B. Our scope of work included drilling one (1) soil boring to a depth of about 15 feet, and drilling two (2) borings to about 5 feet each beneath the existing ground surface at the site.

Our borings were located with a handheld GPS unit and their approximate locations are shown on the Boring Location Diagram in Appendix A. The approximate ground surface elevations shown on the boring logs were selected based on a review of Google Earth terrain elevation data. The precision of this elevation data should be considered approximate.

3.1 SUBSURFACE CHARACTERIZATION

The *Geologic Atlas of Texas – Austin Sheet* indicates that the site is underlain by the Pecan Gap Chalk Formation (Kpg), which generally consists of expansive clays which grade into marl at depth. The approximate location of the site on the geologic map is provided in Appendix A.

The following table provides generalized characterizations of the soil strata encountered during our subsurface exploration. For specific information refer to the boring logs in Appendix B.

STRATUM	APPROXIMATE RANGE OF DEPTH (FEET)	MATERIAL DESCRIPTION	PI ⁽¹⁾ RANGE	PP ⁽²⁾ RANGE	N ⁽³⁾ RANGE
I	0 – (4 to 13.5)	(CH) FAT CLAY WITH SAND; Black to Dark Brown; Firm to Very Stiff	58 – 68	1.0 – 3.0	8 – 18
IIA ⁽⁴⁾	4 – 5.5	(GC) CLAYEY GRAVEL WITH SAND; Light Brown; Loose	21	4.5	8
IIB ⁽⁵⁾	13.5 – 15	MARL; Light Brown; Very Hard			50/6"

- Notes: (1) Plasticity Index
 (2) Standard Penetration Test (SPT) Value, field blows per foot
 (3) Pocket Penetrometer Value, tons per square foot
 (4) Encountered in borings B-02 & B-03
 (5) Encountered in boring B-01

A graphical presentation of the subsurface conditions is shown on the Generalized Subsurface Soil Profile included in Appendix A.

3.2 GROUNDWATER OBSERVATIONS

Groundwater level observations were made in the borings during drilling operations. In air rotary drilling operations, water is not introduced into the borehole and the groundwater position can often be determined by observing water flowing into the excavation. Furthermore, visual observation of soil samples retrieved can often be used in evaluating the groundwater conditions. Groundwater was not encountered during or upon completion of excavation of the borings at the

site. Upon completion of field operations, the boreholes were backfilled with soil cuttings generated during our field operations.

It should be noted that water levels in open excavations may require several hours to several days to stabilize depending on the permeability of the soils and that groundwater levels at the site may be subject to seasonal conditions, recent rainfall, drought or temperature effects. Clays, marl and massive limestone bedrock are generally not conducive to the presence of groundwater; however, gravels, sands and silts, and open fractures and solution features; where present, can store and transmit "perched" groundwater flow or seepage.

The groundwater conditions at this site are expected to be significantly influenced by surface water runoff and rainfall and should therefore be evaluated just prior to construction. Specifically, rainfall that enters the site, either directly from overland flow or adjacent properties, begins to percolate through surficial soils and within granular seams and fissures. This groundwater flow continues downhill with the water table occasionally surfacing to form wet springs and intermittent streams. In low-lying areas and areas adjacent to existing creeks or ponds, shallow groundwater tables can be present continuously.

3.3 LABORATORY TESTING

The laboratory testing was performed by ECS on selected samples obtained during our field exploration operations. Classification and index property tests were performed on representative soil samples obtained from the test borings to aid in classifying soils according to the Unified Soil Classification System and to quantify and correlate engineering properties. The soil samples were tested for moisture content (ASTM D2216), Atterberg limits (ASTM D4318), and gradation (percent passing No. 200 sieve – (ASTM D1140)).

An experienced geotechnical engineer visually classified each soil sample from the test borings on the basis of texture and plasticity in accordance with the Unified Soil Classification System (USCS) and ASTM D2488 (Description and Identification of Soils-Visual/Manual Procedures). After classification, the samples were grouped in the major zones noted on the boring logs in Appendix B. The group symbols for each soil type are indicated in parentheses along with the soil descriptions. The stratification lines between strata on the logs are approximate; in situ, the transitions may be gradual.

The soil samples will be retained in our laboratory for a period of 45 days, after which, they will be discarded unless other instructions are received as to their disposition.

4.0 DESIGN RECOMMENDATIONS

The following recommendations have been developed following the previously described project characteristics and subsurface conditions. If there are any changes to the project characteristics or if different subsurface conditions are encountered during construction, ECS should be consulted so that the recommendations of this report can be reviewed.

4.1 POTENTIAL VERTICAL RISE & SUBGRADE IMPROVEMENTS

Structural damage and/or cosmetic/operational distress can be caused by volume changes in clay soils. The expansive soils found at this site are capable of swelling and shrinking in volume dependent on potentially changing soil water conditions during or after construction. Clays can shrink when they lose water and swell (grow in volume) when they gain water. The potential of expansive clays to shrink and swell is related to; amongst other things, the Plasticity Index (PI). Clays with a higher PI generally have a greater potential for soil volume changes due to moisture content variations.

Several methods exist to evaluate swell potential of expansive clay soils. We have estimated potential heave for this site utilizing the TxDOT PVR method (Tex 124-E). The Tex 124-E method provides an estimate of potential vertical rise (PVR) using the liquid limits, plasticity indices, and existing water contents for soils. The PVR is estimated in the seasonally active zone, which can be up to about 15 feet in the site vicinity, or to a depth of inert material such as marl or limestone bedrock.

Estimated PVR values are based upon assumed typical changes in soil moisture content from a dry (existing) to wet condition; however, soil movements in the field depend on the actual changes in moisture content. Thus, actual soil movements could be less than that calculated if little soil moisture variations occur, or the actual movement could exceed the estimated values if actual soil moisture content changes exceed the PVR methods assumed dry and wet limits. This condition is often the result of excessive droughts, flooding, "perched" groundwater infiltration, poor surface-drainage, excessive irrigation adjacent to building foundations, and/or leaking irrigation lines or plumbing.

We estimate the existing PVR in the proposed building area to be about 6 inches. To reduce the as-built PVR to about 1 inch in the proposed building area, it is recommended that the existing ground surface be undercut as required to allow for either at least 7½ feet of select fill, or 10½ feet of moisture conditioned fill with a 1½ foot select fill cap beneath finished pad grade

In this general area, it is common for structural and geotechnical engineers to consider a PVR of 1 inch to be within acceptable tolerances for properly designed foundation systems. However, this movement does not take into consideration the movement criteria required or perceived by the facility owner or occupants. These "operational" performance criteria may be, and often are, more restrictive than the structural criteria or tolerances.

Grade supported foundation or floor slab movements that approach 1 inch may cause doors to stick, cracks in sheetrock or brittle floor covering, cracks in exterior finishes and other forms of cosmetic distress. Measures can and should be taken during the design and construction of the

facility to help limit the extent and severity of these types of distress. However, these magnitudes of movement typically do not cause "structural distress."

Where movement sensitive flatwork will be constructed adjacent to the building, consideration should be given to reducing the PVR value in the flatwork areas to reduce differential movements and associated door jamming, tripping hazards, etc. Doweling the flatwork to the building foundations at common openings will further help to reduce the potential for differential movements and trip hazards.

4.2 SHALLOW FOUNDATIONS

The planned building can be supported by a monolithic beam with slab-on-grade foundation system.

4.2.1 Slab-on-Grade Foundations

The rigidity of a slab-on-grade foundation system can reduce the effects of differential soil movement due to compression of soils due to structural loads or shrink-swell due to expansive soils. This type of slab can be designed with conventionally reinforced perimeter and interior stiffening grade beams, and/or with post-tensioning adequate to provide sufficient rigidity to the slab element. The grade beam width and depth will be determined by the project Structural Engineer. Grade beams may be thickened and widened at column or load bearing wall locations to support concentrated load areas, if necessary. All grade beams and floor slabs should be adequately reinforced with steel to reduce cracking and support bending moments caused by loading and minor movements of foundation soils.

The design values below are based on the subsurface conditions encountered during this exploration and the recommendations for building pad grading provided herein. If the project information changes, we should be contacted to review; and if necessary, provide alternate design parameters based on the changed conditions. These parameters are provided to assist the Structural Engineer in design of a foundation that is stiffened using grade beams (ribs), post tensioning, or a combination thereof.

POST-TENSIONED SLAB PARAMETERS PTI 3RD EDITION WITH 2008 SUPPLEMENTS	
Design Parameter	1-Inch PVR Design Values
e _m Edge	4.6 Feet
e _m Center	9.0 Feet
y _m Edge	1.4 Inches
y _m Center	1.0 Inches
BRAB/WRI SLAB PARAMETERS	
Design Parameter	1-Inch PVR Design Values
Effective PI	30
Climatic Rating	18
Unconfined Compressive Strength (TSF)	1.5
Soil-Climate Support Index (1-C)	0.16

Grade beams and widened column areas at least 12 inches wide and 18 inches deep can be designed using a net allowable bearing capacity of 3,000 psf. To utilize the parameters listed above, the subgrade should be prepared in accordance with Section 5.0 "Site Construction Recommendations" and the associated subsections of this report, including improving the as-built PVR to 1-inch or better.

Foundations at this site should be expected to undergo some vertical movements. These movements can potentially cause cosmetic distress and must be accounted for in the design process. Contraction, control, or expansion joints should be designed and placed in various portions of the structures. Properly planned placement of these joints will assist in controlling the degree and location of material cracking which normally occurs due to material shrinkage, thermal effects, soil movements, and other related structural conditions.

Where moisture sensitive floor coverings or equipment will be installed, we recommend that at least a 10-mil vapor retarder be used beneath the slabs. The vapor retarder should conform to ASTM E1745, Class C or better and shall have a maximum water vapor permeance of 0.044 when tested in accordance with ASTM E96. Consideration to specifying a thicker, more durable vapor retarder should also be made where anticipated construction traffic dictates. Please refer to the latest edition of ACI 302.2R-06 Guide for Concrete Slabs that Receive Moisture-Sensitive Flooring Materials and ASTM E 1643 Standard Practice for Installation of Water Vapor Retarders Used in Contact with Earth or Granular Fill Under Concrete Slabs for additional guidance on this issue.

4.3 PERIMETER CONDITIONS

The upper 18 inches of soil placed along the exterior of the foundations should consist of lean clayey soils placed and compacted in accordance with this report. The purpose of this clay backfill is to reduce the opportunity for surface or subsurface water infiltration beneath the structure. This clay layer may be replaced with asphalt or concrete pavement that extends to the edge of the structure foundation. Additionally, where penetrations into the structure occur such as utility

trenches, a clay plug (or suitable synthetic alternative) should be placed at the building lines to reduce the opportunity for infiltrating water, regardless of the selected building pad materials. A typical clay plug detail is provided in Appendix D of the report.

Positive drainage away from the structures should also be provided. Soil areas within 10 feet of the building should slope at a minimum of 5 percent away from the structure. Adjacent pavements and concrete hardscape should slope at 1½ to 2 percent away from the structure. Roof leaders and downspouts should discharge onto paved surfaces sloping away from the structure or into a closed pipe system which outfalls to the street gutter pan or directly to the storm drain system.

Additionally, irrigation of lawn and landscaped areas should be moderate, with no excessive wetting or drying of soils around the perimeter of the structures allowed. Trees and bushes/shrubs planted near the perimeter of the structures can withdraw large amounts of water from the soils and should be planted at least one-half their anticipated mature height away from the building. Where flatwork is placed against or near the structure, a positive seal must be installed and adequately maintained to minimize water intrusion.

Routine maintenance is required to ensure that the recommendations contained in this report are followed and maintained. Greater potential movements could occur with extreme wetting or drying of the soils due to poor drainage, ponding of water, plumbing leaks, lack of irrigation, and/or lack of routine maintenance, etc.

4.4 SEISMIC DESIGN CONSIDERATIONS

Seismic Site Classification: The International Building Code (IBC) 2021 requires site classification for seismic design based on the upper 100 feet of a soil profile. Methods are utilized in classifying sites, namely the shear wave velocity (v_s) method and the Standard Penetration Resistance (N-value) method. The seismic site class definitions for the average of shear wave velocity or SPT N-value in the upper 100 feet of the soil profile are shown in the table on the following page.

SEISMIC SITE CLASSIFICATION			
Site Class	Soil Profile Name	Shear Wave Velocity, V_s , (ft./s)	N value (bpf)
A	Hard Rock	$V_s > 5,000$ fps	N/A
B	Rock	$2,500 < V_s \leq 5,000$ fps	N/A
C	Very Dense Soil and Soft Rock	$1,200 < V_s \leq 2,500$ fps	>50
D	Stiff Soil Profile	$600 \leq V_s \leq 1,200$ fps	15 to 50
E	Soft Soil Profile	$V_s < 600$ fps	<15

Based on 2021 International Building Code (IBC) Site Class Definitions, in our opinion the site soil and rock can be characterized as Site Class D. The site class definition should not be confused with the Seismic Design Category designation which the Structural Engineer typically assesses.

In addition to the seismic site classification, ECS has determined the design spectral response acceleration parameters following the IBC methodology. The Mapped Responses were estimated

from the SEAOC OSHPD Seismic Design Maps <https://seismicmaps.org/> using the coordinates Lat: 30.033° N, Long: -97.850° W. The design responses for the short (0.2 sec, S_{DS}) and 1-second period (S_{D1}) are noted in bold at the far-right end of the following table.

GROUND MOTION PARAMETERS [ASCE 7-16 Design Code]								
Period (sec)	Mapped Spectral Response Accelerations (g)		Values of Site Coefficient for Site Class		Maximum Spectral Response Acceleration Adjusted for Site Class (g)		Design Spectral Response Acceleration (g)	
Reference	Figures 1613.3.1 (1) & (2)		Tables 1613.3.3 (1) & (2)		Eqs. 16-37 & 16-38		Eqs. 16-39 & 16-40	
0.2	S_s	0.052	F_a	1.6	$S_{MS}=F_a S_s$	0.083	$S_{DS}=2/3 S_{MS}$	0.055
1.0	S_1	0.029	F_v	2.4	$S_{M1}=F_v S_1$	0.070	$S_{D1}=2/3 S_{M1}$	0.046


4.5 RETAINING WALLS

The magnitude of the lateral earth pressures on retaining walls is dependent upon the in-situ material behind the wall; and if displaced, the type of material used to backfill the “critical zone” behind the wall. The magnitude of the earth pressure is also dependent upon whether the critical zone is allowed to drain water freely. The critical zone can be considered as the area behind the structure within a boundary created by a 45-degree angle extending from the outside edge of the foundation heel upward to the ground surface.

The lateral earth pressures for drained, level soil backfill are expressed in terms of pounds per cubic foot (psf/ft.) “equivalent fluid” weight applied in a triangular distribution pattern as listed below. If the walls are free to deflect or rotate slightly at the top they may be designed using “active” lateral earth pressures. If the walls are laterally restrained at the top, “at-rest” lateral earth pressures should be used for the retaining wall design. Where multiple material types are used within the critical zone, the higher values below should be used. The equivalent fluid weights shown in the table do not include any safety factors and do not account for any surcharges. Lateral loads from uniform surcharges on the wall backfill can be calculated by multiplying the vertical surcharge by the below earth pressure coefficients and should be considered as rectangular loads acting on the full wall height. An increase of 1 pcf and 1.5 pcf should be added to the active and at-rest earth pressures; respectively, for each degree of inclination of backfill.

For the design of site retaining walls, we recommend the soil parameters provided in the following table.

RETAINING WALL BACKFILL IN THE CRITICAL SOIL ZONE				
Soil Parameter	Estimated Value			
Soil Classification	Undisturbed or Compacted Native Soil	Select Fill	ASTM C33 Size #56, #57 or #467 Stone	Compacted Manufactured Sand (< 8% Fines)
Retained Soil Moist Unit Weight (γ)	120 pcf	120 pcf	110 pcf	120 pcf
Angle of Internal Friction (ϕ)	24°	28°	30°	30°
Coefficient of Active Earth Pressure (K_a)	0.42	0.36	0.33	0.33
Coefficient of At-Rest Earth Pressure (K_o)	0.59	0.53	0.50	0.50
Active Equivalent Fluid Pressure	51 (psf/ft)	43 (psf/ft)	37 (psf/ft)	40 (psf/ft)
At-Rest Earth Equivalent Fluid Pressure	71 (psf/ft)	64 (psf/ft)	55 (psf/ft)	60 (psf/ft)



RETAINING WALL FOUNDATIONS	
Parameter	Undisturbed or Compacted Native Soil
Allowable Bearing Pressure	2,000 psf
Minimum Wall Embedment Below Grade	12 inches
Sliding Friction Coefficient [Concrete on Soil or Bedrock] (μ)	0.32
Passive Equivalent Fluid Pressure (Neglect in upper 12 inches)	250 (psf/ft)

It is critical that the soils used for backfill of the retaining walls meet the soil parameters recommended above. If the soils available do not meet those parameters, then ECS should be contacted to provide revised values, and to confirm that only suitable soils will be used for wall backfill.

Care should be used to avoid the operation of heavy equipment to compact the wall backfill since it may overload and damage the wall. In addition, such loads are not typically considered in the design of site retaining walls, and are not provided for in our recommendations.

Wall Drainage: Retaining walls should be provided with a wall and foundation drainage system to relieve hydrostatic pressures which may develop behind the walls. This system can consist of weepholes through the wall and/or a 4-inch perforated, closed joint drain line located along the backside of the walls above the top of the footing. The drain line should be surrounded by a

minimum of 6 inches of AASHTO #57 Stone wrapped with an approved non-woven geotextile, such as Mirafi 140-N, Mirafi 160N or equivalent. Wall drains can consist of a 12-inch wide zone of free draining gravel, such as AASHTO #57 Stone, employed directly behind the wall to within 2 feet of the ground surface and separated from the soils beyond with a non-woven geotextile.

Alternatively, the wall drain can consist of a suitable geocomposite drainage board material such as MiraDRAIN 2000, or reviewed equivalent. The wall drain should be hydraulically connected to the foundation drain. The drainboard should extend from the base of the wall to within two feet of the ground surface, and should be installed in accordance with manufacturer specifications. A subdrain collector pipe surrounded with at least 5 cubic feet per foot size #57 stone (wrapped in filter fabric) should be installed at the base of the drainboard; or alternatively, an engineered system can be selected with sufficient capacity for direct connectivity to a closed pipe system. The groundwater should be conducted to an appropriate discharge or sump pump facility.

4.6 PAVEMENT SECTIONS – PRIVATE DRIVES AND PARKING

ECS has prepared the following recommendations for the design and construction of both flexible and rigid pavement systems for use on the subject project. The “AASHTO Guide for Design of Pavement Structures” published by the American Association of State Highway and Transportation Officials was used to develop the pavement thickness recommendations in this report. This method of design considers pavement performance, traffic, roadbed soil, pavement materials, environment, drainage and reliability. Each of these items is incorporated into the design methodology.

We have based our analysis on the following ESAL information and pavement-related subgrade design parameters, which are considered to be typical for the area. A CBR (California Bearing Ratio) value of 2.0 percent was selected for design purposes. The CBR value was estimated based on ECS’s knowledge and experience with similar soils and projects in this area.

Reliability	70
Initial Serviceability Index, Flexible Pavements	4.2
Initial Serviceability Index, Rigid Pavements	4.5
Terminal Serviceability Index, All Pavements	2.0
Standard Deviation, Flexible Pavements	0.45
Standard Deviation, Rigid Pavements	0.35

Based on the design parameters listed above, we developed recommendations for “light duty,” “moderate duty” and “heavy duty” pavement sections. “Light duty” pavements are intended for general parking areas with passenger vehicles only and have an approximate capacity of 20,000 ESAL. “Moderate duty” pavements are intended for areas subject to channelized traffic and fire

lanes and have an approximate capacity of 80,000 ESAL. "Heavy duty" pavements are intended for areas subject to heavier vehicles with extensive turning, starting and stopping, such as pavement aprons associated with trash enclosures, and have an approximate capacity of 250,000 ESAL. If the owner or other members of the design team feel that the ESAL values used for design are not appropriate, ECS should be notified in writing, so any new information can be reviewed, and if necessary, the pavement recommendations revised accordingly.

The minimum recommended thickness for both hot mixed asphalt concrete (HMAC) and reinforced Portland cement concrete (PCC) pavement sections are presented in the table below for the described "light", "moderate" and "heavy" traffic conditions.

RECOMMENDED PAVEMENT SECTION OPTIONS						
COMPONENT	LIGHT-DUTY 20,000 ESALS		MODERATE-DUTY 80,000 ESALS		HEAVY-DUTY 250,000 ESALS	
	Rigid	Asphalt	Rigid	Asphalt	Rigid	Asphalt
Portland Cement Reinforced Concrete (PCC)	5.0 in	--	6.0 in	--	7.0 in	--
Hot Mixed Asphalt Concrete (HMAC)	--	2.0 in	--	2.5 in	--	--
Crushed Limestone Base (CLB)	--	10.0 in	--	12.0 in	--	--

The pavement sections described above are for general-purpose usage for the anticipated subgrade conditions and were designed using the AASHTO Pavement and Analysis System. An aggressive maintenance program to keep joints and cracks sealed to prevent moisture infiltration will help extend the pavement life.

We recommend that rigid pavement sections be used in all heavy truck traffic areas. The concrete pavement should extend throughout the areas that require extensive turning and maneuvering of the delivery vehicles, etc. Waste dumpster pads, loading areas and other heavily loaded pavement areas that are not designed to accommodate these conditions often experience localized pavement failures, particularly if flexible pavement sections are used.

4.6.1 Pavement Materials

Recommendations regarding material requirements for the various pavement sections are summarized below:

Portland Cement Concrete - Concrete used for paving should have a minimum compressive strength of 3,500 psi at 28-days. The air content at the point of placement should range from 2 to 4 percent. The concrete pavements should be reinforced and jointed per current ACI recommendations.

Hot Mix Asphalt Concrete (HMAC) Surface Course - The asphalt concrete surface course should be plant mixed, hot laid Type D (Fine Graded Surface) or Type C (Coarse Graded Surface Course) meeting the specifications requirements of TxDOT Item 340 and specific criteria for the job mix formula. The mix should be compacted to between 92 and 97 percent of the maximum theoretical density as determined by TEX-227-F.

Crushed Limestone Base Course - Crushed limestone base should be placed in maximum 6-inch compacted lifts. The base materials should be compacted to at least 98 percent of the maximum dry density as determined by TxDOT 113-E. Flexible base materials should be moisture conditioned to between minus two (-2) and plus three (+3) percentage points of the optimum moisture content during compaction. Flexible base materials should meet the requirements specified in 2004 TxDOT Standard Specification Item 247, Type A, Grade 1 or 2.

4.6.2 Rigid Pavement Considerations

Joints are typically placed in rigid pavements to control cracking, to facilitate construction, and to isolate a section of pavement from a structure or an adjacent pavement section. Joints used to control cracking are typically known as contraction or control joints as they are intended to control cracking that arises out of the shrinkage of concrete as it cures. Construction joints are used to provide clean breaks between pavement sections that result from the construction process. Isolation joints (or expansion joints) are used to separate the pavement from other structures or pavements and typically include the use of compressible materials in the joint as opposed to contraction or construction joints. Contraction joints should be spaced no greater than 15 feet between the nearest parallel joints with joint depths of at least one-quarter ($\frac{1}{4}$) of the slab thickness. Contraction and construction joints should be no wider than one-eighth ($\frac{1}{8}$) of an inch whereas isolation joints may be up to one (1) inch wide.

Steel reinforcement is commonly used where subgrade conditions are not likely to provide uniform support to the concrete pavement. Generally, sites with expansive soils present are often unable to provide such support to rigid pavement sections. Therefore, reinforcing steel can be used to span between construction and isolation (expansion) joints and should consist of at-minimum No. 3 bars spaced 18 inches on-centers each way. The rebar should be Grade 60 steel.

As with steel reinforcement, in situations where the subgrade may not provide uniform support to the pavement, dowels are commonly used to transfer loads across joints. Smooth dowels can be used for this purpose and should be utilized as recommended in the following table.

DOWEL DESIGN INFORMATION				
Slab Thickness, In.	Dowel Diameter, in.	Min. Dowel Embedment Each Side, in.	Min. Dowel Length, in.	Dowel Spacing On-Centers, in.
5.0	$\frac{5}{8}$	5	12	12
6.0	$\frac{3}{4}$	6	14	12
7.0	$\frac{7}{8}$	7	16	12

The joint and reinforcing design of a rigid pavement system is largely a function of geometry for the pavement area. The proper length of concrete panels (defined as the distance between discontinuous pavement sections; e.g. between construction or isolation joints, or a combination of the two) and the location of contraction, construction, and isolation (expansion) joints are not included as a function of the above concrete pavement guidelines. Rather, these features should be determined based on the geometry and construction sequencing of the pavement. Actual joint

spacing should be based on actual pavement areas and final panel lengths so that joints are evenly spaced. Joints should be designed to form approximately square panels where geometrically feasible.

The values provided herein are guidelines and the recommendations selected by the project civil engineer and any guidelines not provided or mentioned herein should not exceed the American Concrete Institute (ACI) 330R recommendations.

4.6.3 Pavement Drainage, Subdrainage, and Trenching

Longitudinal cracks and apparent distress due to expansive soils may appear in the pavement after construction and the introduction of landscape irrigation. These cracks and distress are not pavement failures with respect to traffic support, although they may be aesthetically undesirable. In addition, without regular maintenance, the cracks can allow additional moisture intrusion and rapid degradation of the pavement section. The pavement sections are primarily designed to support the traffic and will not resist the forces generated by swelling soils.

Positive drainage should be provided on and around pavement areas to avoid ponding of water. Irrigation of lawn and landscaped areas adjacent to the pavements should be moderate, with no excessive wetting or drying of soils. If landscaped islands are provided, they should be designed to restrict excess water from migrating to the pavement subgrade by using self-contained beds, raised planter boxes, vertical moisture barriers, and/or edge drains. Curbs should extend through the base course and at least 4 inches into the underlying subgrade. Good perimeter surface drainage guiding surface water away from the pavement area is also recommended.

5.0 SITE CONSTRUCTION RECOMMENDATIONS

5.1 SUBGRADE PREPARATION

In a dry and undisturbed state, the upper 1-foot of the soil at the site will provide good subgrade support for fill placement and construction operations. However, when wet, this soil will degrade quickly with disturbance from contractor operations. Therefore, good site drainage should be maintained during earthwork operations, which would help maintain the integrity of the soil. We recommend that an attempt be made to enhance the natural drainage without interrupting its pattern.

The soils at the site are moisture and disturbance-sensitive and contain fines that are considered moderately erodible. Therefore, the contractor should carefully plan his operation to minimize exposure of the subgrade to weather and construction equipment traffic and provide and maintain good site drainage during earthwork operations to help maintain the integrity of the surficial soils. All erosion and sedimentation shall be controlled per sound engineering practice and current jurisdictional requirements.

In preparing the site for construction, all loose or soft existing soils, vegetation, organic soil, existing pavements, foundations or utilities, or other unsuitable materials should be removed from all proposed structural and paving areas, and any areas receiving new fill.

After stripping and any required cuts have been completed, the subgrade soils should be scarified, moisture conditioned and compacted to at least 95 percent of the maximum dry density as determined by TxDOT 114-E to a depth of at least 8 inches. The soils should be moisture conditioned to between optimum and plus four (+4) percentage points of the optimum moisture content just prior to compaction.

5.1.1 Removals, Stripping and Grubbing

The subgrade preparation should consist of stripping all unsuitable materials (as discussed above) 10 feet from the perimeter of the buildings, 5-foot expanded beyond pavement limits, and to 5 feet beyond the toe of structural fills. ECS should be called on to check that topsoil and unsuitable surficial materials have been removed before the placement of fill or construction of structures.

5.1.2 Proof Rolling

After stripping and removing all unsuitable surface materials, cutting to the proposed grade, and before compacting the subgrade or placing of any structural fill, the exposed subgrade should be reviewed by the Geotechnical Engineer or authorized representative. The exposed subgrade should be thoroughly proof rolled with previously approved construction equipment having a minimum axle load of 20 tons (e.g., fully loaded tandem-axle dump truck). The areas subject to proof rolling should be traversed by the equipment in two perpendiculars (orthogonal) directions with overlapping passes of the vehicle under the observation of the Geotechnical Engineer or authorized representative. This procedure is intended to assist in identifying any localized yielding materials. If unstable or "pumping" subgrade is identified by the proof rolling, those areas should be marked for repair before the compacting the subgrade or placing fills or other construction

materials. Methods of repair of unstable subgrade, such as undercutting, moisture conditioning, geogrid or lime/cement stabilization, should be discussed with the Geotechnical Engineer to determine the appropriate procedure about the existing conditions causing the instability.


If the area is deemed too small for a piece of equipment to traverse, the excavated area should be thoroughly probed by the Geotechnical Engineer or authorized representative.

5.1.3 Site Temporary Dewatering

The contractor shall make their own assessment of temporary dewatering needs based upon the limited subsurface groundwater information presented in this report. Soil sampling is not continuous, and thus soil and groundwater conditions may vary between sampling intervals (typically 5 feet). If the contractor believes additional subsurface information is needed to assess dewatering needs, they should obtain such information at their own expense. ECS makes no warranties or guarantees regarding the adequacy of the provided information to determine dewatering requirements; such recommendations are beyond our scope of services.

Dewatering systems are a critical component of many construction projects. Dewatering systems must be selected, designed, and maintained by a qualified and experienced (specialty or other) contractor familiar with the succinct geotechnical and other aspects of the project. The failure to properly design and maintain a dewatering system for a given project can result in delayed construction, unnecessary foundation subgrade undercuts, detrimental phenomena such as 'running sand' conditions, internal erosion (i.e., 'piping'), the migration of 'fines' down-gradient towards the dewatering system, localized settlement of nearby infrastructure, foundations, slabs-on-grade and pavements, etc. Water discharged from any site dewatering system shall be discharged in accordance with all local, state and federal requirements.

Strategies for Addressing Perched Groundwater: The typical primary strategy for addressing perched groundwater seeping into excavations is pumping from trenches (or French drains) and sump pits with sump pumps. A typical sump pump drain (found in a sump pit or along a French drain) is depicted on the following page. The inlet of the sump pump is placed at the bottom of the corrugated pipe and the discharge end of the sump is directed to an appropriate stormwater drain.



Sump Pit/Pump Diagram

A typical French drain consists of an 18-to-24-inch-wide bed of AASHTO #57 (or similar open graded aggregate) aggregate wrapped in a medium duty, non-woven geotextile such as Mirafi 140N or 160N and (often) containing a 4 to 6-inch diameter, Schedule 40 PVC perforated or slotted pipe. Actual dimensions should be as determined necessary by ECS during construction. After the installation has been completed, the geotextile should be wrapped over the top of the aggregate and pipe followed by placement of backfill. The top of the drain should be positioned at least 18 inches beneath the design subgrade elevations. Drains should not be routed within the expanded building limits.

Pumping wells or a vacuum system could also be used to address perched groundwater. These techniques often are only effective during the initial depletion of the perched water quantity and may quickly be ineffective at addressing accumulation of water from rain, lake level, etc.

5.2 EARTHWORK OPERATIONS

To mitigate soil expansion potential in the building areas to about 1 inch, it is recommended that the building pad be improved according to report section 4.1 "Potential Vertical Rise & Subgrade Improvements". The stripping and removal operations and fill placement to finished pad grade should extend at least 5 feet beyond the building perimeters and beneath adjacent movement sensitive concrete flatwork. The upper 18 inches of fill outside of the building area should consist of a properly compacted low permeability clay soil to reduce infiltration of moisture into the adjacent select fill materials.

After stripping and grubbing, undercutting/removals, subgrade preparation (including proof rolling) and evaluation has been completed, fill placement may begin. Fills in the building pad area should consist of materials meeting the requirements of the Select Fill and Moisture Conditioned Fill sections below. Fills in pavement and landscape areas can consist of materials meeting the requirements of the General Fill section below. Consideration should be given to creating an "all weather" working surface with the upper 6 inches of the select fill building pad. Such a working surface should consist of compacted TxDOT Item 247 Type A, Grade 1 or 2 Base material. The use

of an "all weather" working surface can significantly improve the accessibility of the site to construction traffic during periods of wet weather.

Soil moisture levels should be preserved (by various methods that can include covering with plastic, watering, etc.) until new fill, pavements, or slabs are placed. Upon completion of the filling operations, care should be taken to maintain the soil moisture content before the construction of floor slabs and pavements. If the soil becomes desiccated, the affected material should be removed and replaced, or these materials should be scarified, moisture conditioned, and re-compacted.

Utility cuts should not be left open for extended periods and should be properly backfilled. Backfilling should be accomplished with properly compacted on-site soils, rather than granular materials. If granular materials are used, a utility trench cut-off at the building line is recommended to help prevent water from migrating through the utility trench backfill to beneath the proposed structure.

Field density and moisture tests should be performed on each lift as necessary to check that adequate compaction is achieved. As a guide, one test per 5,000 square feet per lift is recommended in the building area (two tests minimum per lift), and one test per 10,000 square feet per lift is recommended for paving areas (two tests minimum per lift). Utility trench backfill should be tested at a rate of one test per lift per every 150 linear feet of the trench (two tests minimum per lift). Certain jurisdictional requirements may require testing in addition to that noted previously. Therefore, these specifications should be reviewed, and more stringent specifications should be followed.

5.3 MATERIAL SPECIFICATIONS

The 'Potential Vertical Rise & Subgrade Improvements' section provided in the 'Design Recommendations' portion of this report outlines the recommendations to improve the PVR in the building area to 1 inch. This section is intended to outline the material requirements of those recommendations.

5.3.1 General Fill

General fill should consist of on-site or imported soils, provided they meet the requirements described below. All general fill materials should be free of organics, construction debris, deleterious materials, and should be free of rocks larger than 4 inches in greatest dimension. Proposed general fill should be evaluated and tested by ECS prior to placement in the field.

ECS recommends that general fill be placed in horizontal loose lifts of not more than 8 inches in thickness. Lift thickness should be decreased when using light compaction equipment. General fill should be compacted to at least 95% of the maximum dry density at moisture contents within the range of optimum to plus four (+4) percentage points of the optimum moisture content (Tex-114-E).

5.3.2 Select Fill

Select fill materials should be free of organics, construction debris, deleterious materials, and should be free of rocks larger than 4 inches in greatest dimension. Select fill should have a Plasticity Index of between 5 and 20. Select fill should be evaluated and tested by ECS prior to placement in the field.

ECS recommends that select fill be placed in horizontal loose lifts of not more than 8 inches in thickness. Select fill should be compacted to at least 95% of the maximum dry density at moisture contents within the range of minus one (-1) to plus three (+3) percentage points of the optimum moisture content (Tex-114-E).

5.3.3 Moisture Conditioned Fill

Moisture conditioned fill materials for use in PVR mitigation should be clean of organics, construction debris, deleterious materials, and should contain less than 15 percent gravel (material retained on the No. 4 sieve (by dry unit weight)). Material proposed for use as moisture conditioned fill should be relatively uniform in composition and should be evaluated and tested by ECS in the laboratory prior to placement in the field.

ECS recommends that moisture conditioned fill be placed in horizontal loose lifts of not more than 8 inches in thickness. Moisture conditioned fill for the purposes of PVR reduction in the building pads should be compacted to between 88% and 95% of the maximum dry density TEX-113-E at moisture contents demonstrated to limit swell or consolidation to less than 0.75 percent at the modeled in-situ overburden pressures (ASTM D4546).

ECS recommends that moisture-density relationships and swell test bulk samples be collected for soils proposed for moisture conditioned fill approximately 1 to 2 weeks prior to commencement of earthwork operations. Moisture conditioning recommendations may need to be adjusted based upon testing performed during construction. It is recommended that moisture conditioned building pads have slab-on-grade constructed as soon as possible after grading in an effort to seal in the moisture and reduce evapotranspiration. Owners and landscape architects should be advised that trees should not be located closer than one-half their mature height from the foundations.

If the moisture conditioned fill option is implemented to reduce the PVR, the earthwork contractor should be aware that there is a high probability that soils placed in the building pads will be compacted at well above their optimum moisture content. Soils compacted several percentage points above their optimum moisture content are typically soft and susceptible to rutting, and appropriate construction equipment capable of maneuvering on soft ground conditions should be considered.

5.4 FOUNDATION AND SLAB OBSERVATIONS

Protection of Foundation Excavations: Exposure to the environment may weaken the soils at the footing bearing level if the foundation excavations remain open for too long a time. Therefore, foundation concrete should be placed as soon as possible after the excavations are made. If the bearing soils are softened by surface water intrusion or exposure, the softened soils must be

removed from the foundation excavation bottom immediately prior to placement of concrete. If the excavation must remain open overnight, or if rainfall becomes imminent while the bearing soils are exposed, a 1 to 3-inch thick "mud mat" of "lean" concrete is suggested to be placed on the bearing soils before the placement of reinforcing steel.

Footing and Slab Subgrade Observations: It is important to have ECS observe the foundation subgrade prior to placing foundation concrete, to confirm the bearing soils are what was anticipated.

5.5 UTILITY INSTALLATIONS

Utility Subgrades: The soils encountered in our exploration are expected to be generally suitable for support of utility pipes. The pipe subgrades should be observed and probed for stability by ECS. Any loose or unsuitable materials encountered should be removed and replaced with suitable compacted General Fill, or pipe stone bedding material.

Utility Backfilling: The granular bedding material (often AASHTO #57 stone or sand) should be at least 4 inches thick, but not less than that specified by the civil engineer's project drawings and specifications. We recommend that the bedding materials be placed up to at least the springline of the pipe. Utility trenches in the building pads should be backfilled above the utility bedding and shading materials with similar materials to original building pad construction, and general fill materials outside the building pad areas. The backfill materials should be placed in lifts not to exceed 8 inches loose measure, or 6 inches compacted measure. Thinner lifts may be required when using handheld compaction equipment. Backfill materials should be moisture conditioned and compacted in accordance with the moisture conditioned fill, select fill and general fill sections of this report. Where building pads have been constructed using moisture conditioned soils and a select fill cap, care should be exercised to separate out these materials during trenching and place them back in a similar manner to original building pad construction. Mixing of these two soils types should be prevented.

Utility Connections: Flexible connections should be considered where utilities connect to the buildings or pass-through building foundations/slabs to allow for the anticipated Potential Vertical Rise differential. This could be provided by special flexible connections, pipe sleeving with appropriate waterproofing, or other methods.

Excavation Safety: All excavations and slopes should be constructed and maintained in accordance with OSHA excavation safety standards. The contractor is solely responsible for designing, constructing, and maintaining stable temporary excavations and slopes. The contractor's responsible person, as defined in 29 CFR Part 1926, should evaluate the soil exposed in the excavations as part of the contractor's safety procedures. In no case should slope height, slope inclination, or excavation depth, including utility trench excavation depth, exceed those specified in local, state, and federal safety regulations. ECS is providing this information solely as a service to our client. ECS is not assuming responsibility for construction site safety or the contractor's activities; such responsibility is not being implied and should not be inferred.

6.0 CLOSING

ECS has prepared this report to guide the geotechnical-related design and construction aspects of the project. We performed these services in accordance with the standard of care expected of professionals in the industry performing similar services on projects of like size and complexity at this time in the region. No other representation expressed or implied, and no warranty or guarantee is included or intended in this report.

The description of the proposed project is based on information provided to ECS by Client. If any of this information is inaccurate or changes, either because of our interpretation of the documents provided or site or design changes that may occur later, ECS should be contacted so we can review our recommendations and provide additional or alternate recommendations that reflect the proposed construction.

We recommend that ECS review the project plans and specifications so we can confirm that those plans/specifications are in accordance with the recommendations of this geotechnical report.

Field observations, and quality assurance testing during earthwork and foundation installation are an extension of, and integral to, the geotechnical design. We recommend that ECS be retained to apply our expertise throughout the geotechnical phases of construction, and to provide consultation and recommendation should issues arise.

ECS is not responsible for the conclusions, opinions, or recommendations of others based on the data in this report.

The analysis and recommendations submitted in this report are based upon the data obtained from the soil borings and tests performed at the locations as indicated on the Boring Location Diagram and other information referenced in this report. This report does not reflect any variations, which may occur between the borings. In the performance of the subsurface exploration, specific information is obtained at specific locations at specific times. However, it is a well-known fact that variations in subsurface conditions exist on most sites between boring locations and also such situations as groundwater levels vary from time to time. The nature and extent of variations may not become evident until the course of construction. If variations then appear evident, after performing on-site observations during the construction period and noting characteristics and variations, a reevaluation of the recommendations for this report will be necessary.

APPENDIX A – Figures


Site Location Diagram

Boring Location Diagram

Generalized Subsurface Soil Profile

Site Geologic Map

Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors





SITE LOCATION DIAGRAM ZAXBY'S RESTAURANT

NORTH OF 19140 I-35, KYLE, TEXAS
CARTER ENGINEERING CONSULTANTS, INC.



ENGINEER MMS1
SCALE AS NOTED
PROJECT NO. 17:5744
SHEET 1 OF 1
DATE NOVEMBER 2021

Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors



Legend



Approximate Boring Locations




Approximate Cross-Section Locations






BORING LOCATION DIAGRAM ZAXBY'S RESTAURANT

NORTH OF 19140 I-35, KYLE, TEXAS
CARTER ENGINEERING CONSULTANTS, INC.

ENGINEER MMS1
SCALE AS NOTED
PROJECT NO. 17:5744
SHEET 1 OF 1
DATE NOVEMBER 2021



Legend Key

-  Fat CLAY
-  CLAYEY GRAVEL
-  Limestone

Notes:
 1- EOB: END OF BORING AR: AUGER REFUSAL SR: SAMPLER REFUSAL.
 2- THE NUMBER BELOW THE STRIPS IS THE DISTANCE ALONG THE BASELINE.
 3- SEE INDIVIDUAL BORING LOG AND GEOTECHNICAL INFORMATION.
 4- STANDARD PENETRATION TEST RESISTANCE (LEFT OF BORING) IN BLOWS PER FOOT (ASTM D1586).


Plastic Limit	Water Content	Liquid Limit	▽	WL (First Encountered)	■	Fill
X	●	△	▽	WL (Completion)	■	Possible Fill
[FINES CONTENT %]			▽	WL (Seasonal High Water)	■	Probable Fill
◀	BOTTOM OF CASING	▽	▽	WL (Stabilized)	■	Rock
⊞	LOSS OF CIRCULATION					



GENERALIZED SUBSURFACE SOIL PROFILE Section Line 1


Zaxby's Restaurant
Carter Engineering Consultants, Inc.
North of 19140 I-35, Kyle, Texas 78640

Project No: 17-5744 Date: NOVEMBER 2021



**Austin Chalk Formation (Kau)
Pecan Gap Formation (Kpg)**

Geologic Atlas of Texas, Austin Sheet UT Bureau of Economic Geology, 1974



ECS-SOUTHWEST, LLP

14050 Summit Drive, Suite 101
Austin, Texas 78728



FIG 4: Site Geologic Map

Proposed Zaxby's Restaurant
North of 19140 I-35
Kyle, Texas

SCALE: NTS

PROJECT No.: 17-5744

DATE: NOVEMBER 2021

PM:TM

FIGURE: 4

APPENDIX B – Field Operations

Reference Notes for Boring Logs
Boring Logs B-01 to B-03

REFERENCE NOTES FOR BORING LOGS

MATERIAL ^{1,2}	
	ASPHALT
	CONCRETE
	GRAVEL
	TOPSOIL
	VOID
	BRICK
	AGGREGATE BASE COURSE
	GW WELL-GRADED GRAVEL gravel-sand mixtures, little or no fines
	GP POORLY-GRADED GRAVEL gravel-sand mixtures, little or no fines
	GM SILTY GRAVEL gravel-sand-silt mixtures
	GC CLAYEY GRAVEL gravel-sand-clay mixtures
	SW WELL-GRADED SAND gravelly sand, little or no fines
	SP POORLY-GRADED SAND gravelly sand, little or no fines
	SM SILTY SAND sand-silt mixtures
	SC CLAYEY SAND sand-clay mixtures
	ML SILT non-plastic to medium plasticity
	MH ELASTIC SILT high plasticity
	CL LEAN CLAY low to medium plasticity
	CH FAT CLAY high plasticity
	OL ORGANIC SILT or CLAY non-plastic to low plasticity
	OH ORGANIC SILT or CLAY high plasticity
	PT PEAT highly organic soils

DRILLING SAMPLING SYMBOLS & ABBREVIATIONS			
SS	Split Spoon Sampler	PM	Pressuremeter Test
ST	Shelby Tube Sampler	RD	Rock Bit Drilling
WS	Wash Sample	RC	Rock Core, NX, BX, AX
BS	Bulk Sample of Cuttings	REC	Rock Sample Recovery %
PA	Power Auger (no sample)	RQD	Rock Quality Designation %
HSA	Hollow Stem Auger		

PARTICLE SIZE IDENTIFICATION		
DESIGNATION	PARTICLE SIZES	
Boulders	12 inches (300 mm) or larger	
Cobbles	3 inches to 12 inches (75 mm to 300 mm)	
Gravel:	Coarse	¾ inch to 3 inches (19 mm to 75 mm)
	Fine	4.75 mm to 19 mm (No. 4 sieve to ¾ inch)
Sand:	Coarse	2.00 mm to 4.75 mm (No. 10 to No. 4 sieve)
	Medium	0.425 mm to 2.00 mm (No. 40 to No. 10 sieve)
	Fine	0.074 mm to 0.425 mm (No. 200 to No. 40 sieve)
Silt & Clay ("Fines")	<0.074 mm (smaller than a No. 200 sieve)	

COHESIVE SILTS & CLAYS		
UNCONFINED COMPRESSIVE STRENGTH, QP ⁴	SPT ⁵ (BPF)	CONSISTENCY ⁷ (COHESIVE)
<0.25	<2	Very Soft
0.25 - <0.50	2 - 4	Soft
0.50 - <1.00	5 - 8	Firm
1.00 - <2.00	9 - 15	Stiff
2.00 - <4.00	16 - 30	Very Stiff
4.00 - 8.00	31 - 50	Hard
>8.00	>50	Very Hard

RELATIVE AMOUNT ⁷	COARSE GRAINED (%) ⁸	FINE GRAINED (%) ⁸
Trace	≤5	≤5
With	10 - 20	10 - 25
Adjective (ex: "Silty")	25 - 45	30 - 45

GRAVELS, SANDS & NON-COHESIVE SILTS	
SPT ⁵	DENSITY
<5	Very Loose
5 - 10	Loose
11 - 30	Medium Dense
31 - 50	Dense
>50	Very Dense

WATER LEVELS ⁶	
	WL (First Encountered)
	WL (Completion)
	WL (Seasonal High Water)
	WL (Stabilized)

FILL AND ROCK			
FILL	POSSIBLE FILL	PROBABLE FILL	ROCK

¹Classifications and symbols per ASTM D 2488-17 (Visual-Manual Procedure) unless noted otherwise.

²To be consistent with general practice, "POORLY GRADED" has been removed from GP, GP-GM, GP-GC, SP, SP-SM, SP-SC soil types on the boring logs.

³Non-ASTM designations are included in soil descriptions and symbols along with ASTM symbol [Ex: (SM-FILL)].

⁴Typically estimated via pocket penetrometer or Torvane shear test and expressed in tons per square foot (tsf).

⁵Standard Penetration Test (SPT) refers to the number of hammer blows (blow count) of a 140 lb. hammer falling 30 inches on a 2 inch OD split spoon sampler required to drive the sampler 12 inches (ASTM D 1586). "N-value" is another term for "blow count" and is expressed in blows per foot (bpf). SPT correlations per 7.4.2 Method B and need to be corrected if using an auto hammer.


⁶The water levels are those levels actually measured in the borehole at the times indicated by the symbol. The measurements are relatively reliable when augering, without adding fluids, in granular soils. In clay and cohesive silts, the determination of water levels may require several days for the water level to stabilize. In such cases, additional methods of measurement are generally employed.

⁷Minor deviation from ASTM D 2488-17 Note 14.

⁸Percentages are estimated to the nearest 5% per ASTM D 2488-17.

SITE LOCATION:
North of 19140 I-35, Kyle, Texas 78640

NORTHING: 3043119.9	EASTING: 939629.5	STATION:	SURFACE ELEVATION: 722.0	LOSS OF CIRCULATION
				BOTTOM OF CASING



THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES. IN-SITU THE TRANSITION MAY BE GRADUAL

<input checked="" type="checkbox"/> WL (First Encountered)	BORING STARTED: Nov 02 2021	CAVE IN DEPTH:
<input checked="" type="checkbox"/> WL (Completion) Dry	BORING COMPLETED: Nov 02 2021	HAMMER TYPE: Auto
<input checked="" type="checkbox"/> WL (Seasonal High Water)	EQUIPMENT: Truck CME-45	LOGGED BY:
<input checked="" type="checkbox"/> WL (Stabilized)		DRILLING METHOD: Air Rotary

GEOTECHNICAL BOREHOLE LOG

SITE LOCATION:
North of 19140 I-35, Kyle, Texas 78640

NORTHING: 3043121.8	EASTING: 939665.0	STATION:	SURFACE ELEVATION: 722.0	LOSS OF CIRCULATION
				BOTTOM OF CASING

DEPTH (FT)	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE DIST. (IN)	RECOVERY (IN)	DESCRIPTION OF MATERIAL	WATER LEVELS	ELEVATION (FT)	BLOWS/6"	Plastic Limit Water Content Liquid Limit X ● ———— △ <input checked="" type="checkbox"/> STANDARD PENETRATION BLOWS/FT ROCK QUALITY DESIGNATION & RECOVERY — RQD — REC <input type="checkbox"/> CALIBRATED PENETROMETER TON/SF [FINES CONTENT] %
	S-1	ST	24	24	(CH) FAT CLAY WITH SAND, dark brown, stiff to very stiff				Plastic Limit Water Content Liquid Limit X ● ———— △ <input checked="" type="checkbox"/> STANDARD PENETRATION BLOWS/FT ROCK QUALITY DESIGNATION & RECOVERY — RQD — REC <input type="checkbox"/> CALIBRATED PENETROMETER TON/SF [FINES CONTENT] %
	S-2	ST	24	24					
5	S-3	SS	18	18	(GC) CLAYEY GRAVEL WITH SAND, light brown, loose		717	9-5-3 (8)	Plastic Limit Water Content Liquid Limit X ● ———— △ <input checked="" type="checkbox"/> STANDARD PENETRATION BLOWS/FT ROCK QUALITY DESIGNATION & RECOVERY — RQD — REC <input type="checkbox"/> CALIBRATED PENETROMETER TON/SF [FINES CONTENT] %
					END OF DRILLING AT 5.5 FT				
10							712		
15							707		
20							702		
25							697		
30							692		



THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES. IN-SITU THE TRANSITION MAY BE GRADUAL

<input checked="" type="checkbox"/> WL (First Encountered)	BORING STARTED: Nov 02 2021	CAVE IN DEPTH:
<input checked="" type="checkbox"/> WL (Completion) Dry	BORING COMPLETED: Nov 02 2021	HAMMER TYPE: Auto
<input checked="" type="checkbox"/> WL (Seasonal High Water)	EQUIPMENT: Truck CME-45	LOGGED BY:
<input checked="" type="checkbox"/> WL (Stabilized)		DRILLING METHOD: Air Rotary

GEOTECHNICAL BOREHOLE LOG

SITE LOCATION:
North of 19140 I-35, Kyle, Texas 78640

NORTHING: 3043114.8	EASTING: 939589.8	STATION:	SURFACE ELEVATION: 721.0	LOSS OF CIRCULATION 
				BOTTOM OF CASING 

DEPTH (FT)	SAMPLE NUMBER	SAMPLE TYPE	SAMPLE DIST. (IN)	RECOVERY (IN)	DESCRIPTION OF MATERIAL	WATER LEVELS	ELEVATION (FT)	BLOWS/6"	Plastic Limit Water Content Liquid Limit X ● ———— △ ⊗ STANDARD PENETRATION BLOWS/FT ROCK QUALITY DESIGNATION & RECOVERY — RQD — REC ○ CALIBRATED PENETROMETER TON/SF [FINES CONTENT] %	
	S-1	SS	18	18	(CH) FAT CLAY WITH SAND, dark brown to light brown, stiff to very stiff			4-3-5 (8)		
	S-2	SS	18	18						5-8-10 (18)
5	S-3	ST	18	18			(GC) CLAYEY GRAVEL WITH SAND, light brown, calcareous			716
					END OF DRILLING AT 5.0 FT					
10										
15										
20										
25										
30										

THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL TYPES. IN-SITU THE TRANSITION MAY BE GRADUAL

<input checked="" type="checkbox"/> WL (First Encountered)	BORING STARTED: Nov 02 2021	CAVE IN DEPTH:
<input checked="" type="checkbox"/> WL (Completion) Dry	BORING COMPLETED: Nov 02 2021	HAMMER TYPE: Auto
<input checked="" type="checkbox"/> WL (Seasonal High Water)	EQUIPMENT: Truck CME-45	LOGGED BY:
<input checked="" type="checkbox"/> WL (Stabilized)		DRILLING METHOD: Air Rotary

GEOTECHNICAL BOREHOLE LOG

APPENDIX C – Laboratory Testing

Laboratory Testing Summary
Grain Size Distributions

Laboratory Testing Summary

Sample Source	Sample Number	Start Depth (feet)	End Depth (feet)	Sample Distance (feet)	MC ¹ (%)	Soil Type ²	Atterberg Limits ³			Percent Passing No. 200 Sieve ⁴	Moisture - Density (Corr.) ⁵		CBR Value ⁶	Organic Content
							LL	PL	PI		Maximum Density (pcf)	Optimum Moisture (%)		
B-01	S-2	2.0	4.0	2.0	24.7	CH	76	18	58	82.9				
B-01	S-4	6.0	8.0	2.0	40.8		91	23	68					
B-02	S-3	4.0	5.5	1.5	13.2		35	14	21	30.6				
B-03	S-2	2.0	4.0	2.0	22.1									

Notes: 1. ASTM D 2216, 2. ASTM D 2487, 3. ASTM D 4318, 4. ASTM D 1140, 5. See test reports for test method, 6. See test reports for test method

Definitions: MC: Moisture Content, Soil Type: USCS (Unified Soil Classification System), LL: Liquid Limit, PL: Plastic Limit, PI: Plasticity Index, CBR: California Bearing Ration, OC: Organic Content (ASTM D 2974)

Project No. 17:5744
Project Name: Zaxby's Restaurant
PM: Timothy Moody
PE: Michael Sorgenfrei
Printed On: November 16, 2021

ECS Southwest, LLP - Austin

14050 Summit Drive Suite 101,
Austin, TX 78728

Phone: 512-837-8005
Fax: 512-388-8914

Grain Size Distributions

<u>Boring</u>	<u>Depth</u>	<u>% Fines</u>	<u>% Gravel</u>	<u>% Sand</u>	<u>USCS Soil Type</u>
B-1	2-4	82.9	7.2	9.8	(CH) FAT CLAY WITH SAND
B-2	4-6	30.6	48.3	21.1	(GC) CLAYEY GRAVEL WITH SAND



ECS Southwest, LLP
 14050 Summit Drive, Suite 101
 Austin, Texas 78728


Zaxby's Restaurant
 North of 19140 I-35
 Kyle, Texas


Project Number: 17:5744 | Date: November 2021

APPENDIX D – Supplemental Report Documents

Clay Plug Detail

REFER TO MEP AND/OR CIVIL DRAWINGS FOR TYPICAL BEDDING MATERIALS AT EXTERIOR FACE OF BUILDING. REPLACE BEDDING MATERIALS WITH CLAY SOIL. EXTEND CLAY 7 FEET FROM BUILDING. PLACE IN 8" MAX. LOOSE LIFTS. COMPACT TO GENERAL FILL SPECIFICATIONS PER GEOTECHNICAL REPORT. USE CARE AS TO NOT DAMAGE THE UTILITY DURING BACKFILLING.



	Title: CLAY PLUG DETAIL		Project: Zaxby's Restaurant North of 19140 I-35 Kyle, Texas	
	ECS Southwest, LLP 14050 Summit Drive, Suite 101 Austin Texas 78728		Notes:	
	Project No.: 17-5744	Date: NOV. 2021	Scale: NTS	Figure No. 5